

LEBANESE SUSTAINABLE ENERGY

للبنانية للطاقة البديلة

CONVENTIONAL
ECONOMY SYSTEM

NO AP05/24

Lebanese Sustainable Energy - Riad Soloh street / Bustan Bld / Tripoli -Lebanon / Tel 70-001747 / 06-205492

Quotation
STANDARD 1

Project 60A Peak Load 20A x 3 / Average 75%: 16A Nominal Load -20160W OFF-GRID COMPLETE SYSTEM
System Indoor or Outdoor installation **Estimated Battery Lifetime 60months on average**

Model EOFFG60S1- Standard1 Size **PRICING** 15/5/2024
BATT.TYPE LITHIUM LiFep04 Battery (Wall Mount) **VALID**

RANGE LOC Lebanon - up to 200m above the sea **HIGH FREQUENCY INVERTER SYSTEM**

G.NOTES
* Transportation & Handling Fees covers North coast areas down to Damour zone and/or (Up to 200M above sea level)
* Battery rack & inverter mount are optional for all Hybrid High/Low Frequency applications.
* Cabling pricing are not included. Cabling final pricing are based to distance needed

I.Code	Technical Description	QTY	Unit/ Price \$	Total USD
SPF-6000	GROWATT 6000W 48vdc High-Frequency Off Grid Solar inverter/ 2 MPPT 100A- 120-430 VDC	3	\$778.00	\$778.00
Pk4.8k	Pkenergy Lithium Battery_LiFep04 100Ah- 4.8kWh / 48VDC 6000Cycle @80% DoD / Wall Mount	6	\$1,150.00	\$6,900
CBL25C	25mm Copper Single Line (Black Red) for Battery wiring	96m	\$4.48	\$430
COS25	25mm/ open 8mm Cos type battery clamp.	66	\$0.36	\$24
MCCB10	MCCB DC Battery Circuit Breaker (Common) 120A VDC	6	\$32.00	\$192
BT8- INVT	8- Battery rack & inverter back holder "table manner" (Steel) in white color (Optional)	1	\$218.00	\$218
BT8	8- Battery rack - "table manner" only (Steel) in white color (Optional)	2	\$128.00	\$256
ATS-1P	ATS (Complete) up to 80A max mono phase	1 setup	\$210	\$210.00
DSP-1P	Indoor Control Display- Multiple in-out AMP & Volt Meter protection + C.Breakers	1 setup	\$100.00	\$100.00
LBC6.0-4	6.0mm x 4 lines Power Cable on grid (White Color).	Per 1/m	\$8.80	\$0.00
ROS560	ROSEN 560w HafCell MonoC. PERC Photovoltaic Solar Panel Premium Class A	36 Panels	\$116.00	\$4,176
S-RACK	Customized Fortified,Rust Resistant Rack+ Complete Base& Setup+ all accessories.	36 Panels	\$55.00	\$1,980
S-RACK-INST	Outdoor Solar Rack assembly & Welding works including labour and other installation.	36 Panels	\$10.00	\$360
CB-VP	Panel DC-Circuit Breaker - Multi Surge Protective Panel Circuit Indoor Panel board	3 setup	\$78.00	\$234
TRSD25M	Liban Cable - TORSAD E Aluminium Panel2MPPT Black outdoor cable (16mm x 2)	Per 1/M	\$1.00	\$0
TRSD25M	Liban Cable or Comm Scope Italy - PV Solar Cable- Copper DoubleShield 6mm	Per 1/M	\$3.40	\$0
OUTBX1	(13x13x7) Outdoor Junction Box + Copper Twin wire screw connectors. (25mm)	1	\$8.00	\$0
ACCS1	Outdoor/ Indoor accessories:(Roll Bolt Screw, Cable tie, Wire Fastner, Nail Plugs)	Complete	\$13.00	\$13
TRSP	General Handling charges & Transportation that includes outdoor panel racks material	1 setup	\$500.00	\$500.00
INST	Complete Installation (Indoor / Outdoor)	1 setup	\$1,400.00	\$1,400.00
WRTY201	ALL TECH INSURANCE (Risk Cover) & Free maintenance + Follow up vists	24 MONTHS	INCLUDED	INCLUDED
WRTY201	ALL TECH Tubular Tall Lead Acid BATTERY INSURANCE / EXCHANGE & REPAIR	60 MONTHS	INCLUDED	INCLUDED

TOTAL AMOUNT US \$17,771.00
Discount % USD \$0.00
NET TOTAL AMOUNT \$17,771.00

Duration Battery Consumption time-frame @75% 48A constant load from fully charged down to 80% depth of discharge: 2.6hrs

NOTE Prices includes the ALL TECH INSURANCE (REF.CODE201)

Payment 80% upon agreement/ 20% upon delivery
Q,Validity Prices are subject to change without further notice

www.lse.com.lb